

Summit Scientific

4653 Table Mountain Drive, Golden, Colorado 80403

303.277.9310

September 23, 2024

Paul Henchan
Fremont Environmental
PO Box 1289
Wellington, CO 80549

RE: Noble - Ocoma C17-15/TB (Background)

Work Order #2409199

Enclosed are the results of analyses for samples received by Summit Scientific on 09/13/24 16:30. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

A handwritten signature in black ink, appearing to read "Natalie Tessier". The signature is written in a cursive, flowing style.

Natalie Tessier For Paul Shrewsbury
President



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
Project Manager: Paul Henchan

Reported:
09/23/24 08:40

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
BKG1 2FT	2409199-01	Soil	09/10/24 00:00	09/13/24 16:30
BKG2 2FT	2409199-02	Soil	09/10/24 00:00	09/13/24 16:30
BKG3 2FT	2409199-03	Soil	09/10/24 00:00	09/13/24 16:30
BKG4 2FT	2409199-04	Soil	09/10/24 00:00	09/13/24 16:30
BKG5 2FT	2409199-05	Soil	09/10/24 00:00	09/13/24 16:30

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

S₂

Sample Receipt Checklist

S2 Work Order# 2409199

Client: Fremont Client Project ID: NOI - Ocoma C17-19/TB (Background)

Shipped Via: H.D./P.U./FedEx/UPS/USPS/Other Airbill #: _____

Matrix (Check all that apply) Air Soil/Solid Water Other

Temp (°C) Thermometer #

	Yes	No	N/A	Comments (if any)
If samples require cooling, is the temperature < 6°C? ⁽¹⁾ NOTE: If samples are delivered the same day of sampling, this requirement is met if there is evidence that cooling has begun.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	OK
If custody seals are present, are they intact? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Are samples due within 48 hours present?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Are water samples with short hold times present? Note the short hold analysis in the comments column - pH, Nitrate/Nitrite, Ferrous Iron (Fe ²⁺), Hexavalent Chromium (Cr ⁶⁺ , Cr VI), COD/BOD, Total Coliform, E. Coli, Total Residual Chlorine (TRC), Dissolved Oxygen	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Is a chain-of-custody (COC) form present and filled out Completely? ⁽¹⁾	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Is the COC properly relinquished by the client w/ date and time recorded? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Were all samples received intact? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Was adequate sample volume provided? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Does the COC agree with the number and type of sample bottles received? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Do the sample IDs on the bottle labels match the COC? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
For volatiles in water – is there headspace present? If yes, contact client and note in narrative.	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Are samples preserved that require preservation (excluding cooling)? ⁽¹⁾ Note the type of preservative in the comments column – HCl, H ₂ SO ₄ , NaOH, HNO ₃ , etc.	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
If samples are acid preserved for metals, is the pH ≤ 2? ⁽¹⁾ Record the pH in Comments.	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
If dissolved metals are requested, were samples field filtered?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Additional Comments (if any): <u>inappropriate bottleware - requires qualifiers</u>				
⁽¹⁾ If NO, then contact the client before proceeding with analysis and note in case narrative.				

AS
Custodian Printed Name

9/13/24
Date/Time



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
Project Manager: Paul Henchan

Reported:
09/23/24 08:40

BKG1 2FT
2409199-01 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Boron	ND	2.00		mg/L	1	BHI0492	09/16/24	09/17/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Arsenic	0.732	0.200		mg/kg dry	1	BHI0483	09/16/24	09/18/24	EPA 6020B	
Barium	51.6	0.400		"	"	"	"	"	"	
Cadmium	ND	0.200		"	"	"	"	"	"	
Copper	1.64	0.400		"	"	"	"	"	"	
Lead	4.74	0.200		"	"	"	"	"	"	
Nickel	1.69	0.400		"	"	"	"	"	"	
Silver	0.0337	0.0200		"	"	"	"	"	"	
Zinc	7.13	0.400		"	"	"	"	"	"	
Selenium	ND	0.260		"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chromium, Hexavalent	ND	0.30		mg/kg dry	1	BHI0541	09/17/24	09/17/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Calcium	188	0.0500		mg/L dry	1	BHI0565	09/17/24	09/19/24	EPA 6020B	
Magnesium	36.1	0.0500		"	"	"	"	"	"	
Sodium	11.6	0.0500		"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

BKG1 2FT
2409199-01 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	0.203	0.00100	units	1	BHI0688	09/20/24	09/20/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	96.2		%	1	BHI0497	09/16/24	09/18/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.120	0.0100	mmhos/cm	1	BHI0616	09/18/24	09/19/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.47		pH Units	1	BHI0617	09/18/24	09/19/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
Project Manager: Paul Henchan

Reported:
09/23/24 08:40

BKG2 2FT
2409199-02 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Boron	ND	2.00		mg/L	1	BHI0492	09/16/24	09/17/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Arsenic	0.754	0.200		mg/kg dry	1	BHI0483	09/16/24	09/18/24	EPA 6020B	
Barium	46.2	0.400		"	"	"	"	"	"	
Cadmium	ND	0.200		"	"	"	"	"	"	
Copper	1.12	0.400		"	"	"	"	"	"	
Lead	4.10	0.200		"	"	"	"	"	"	
Nickel	1.54	0.400		"	"	"	"	"	"	
Silver	0.0321	0.0200		"	"	"	"	"	"	
Zinc	5.51	0.400		"	"	"	"	"	"	
Selenium	ND	0.260		"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chromium, Hexavalent	ND	0.30		mg/kg dry	1	BHI0541	09/17/24	09/17/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Calcium	173	0.0500		mg/L dry	1	BHI0565	09/17/24	09/19/24	EPA 6020B	
Magnesium	72.7	0.0500		"	"	"	"	"	"	
Sodium	161	0.0500		"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

BKG2 2FT
2409199-02 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	2.59	0.00100	units	1	BHI0688	09/20/24	09/20/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	98.5		%	1	BHI0497	09/16/24	09/18/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	2.04	0.0100	mmhos/cm	1	BHI0616	09/18/24	09/19/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	7.87		pH Units	1	BHI0617	09/18/24	09/19/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
Project Manager: Paul Henchan

Reported:
09/23/24 08:40

BKG3 2FT
2409199-03 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Boron	ND	2.00	mg/L	1	BHI0492	09/16/24	09/17/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Arsenic	0.560	0.200	mg/kg dry	1	BHI0483	09/16/24	09/18/24	EPA 6020B	
Barium	30.3	0.400	"	"	"	"	"	"	
Cadmium	ND	0.200	"	"	"	"	"	"	
Copper	0.958	0.400	"	"	"	"	"	"	
Lead	3.45	0.200	"	"	"	"	"	"	
Nickel	1.19	0.400	"	"	"	"	"	"	
Silver	ND	0.0200	"	"	"	"	"	"	
Zinc	4.64	0.400	"	"	"	"	"	"	
Selenium	ND	0.260	"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Chromium, Hexavalent	ND	0.30	mg/kg dry	1	BHI0541	09/17/24	09/17/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Calcium	102	0.0500	mg/L dry	1	BHI0565	09/17/24	09/19/24	EPA 6020B	
Magnesium	48.5	0.0500	"	"	"	"	"	"	
Sodium	353	0.0500	"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.





Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

BKG3 2FT
2409199-03 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	7.21	0.00100	units	1	BHI0688	09/20/24	09/20/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	98.2		%	1	BHI0497	09/16/24	09/18/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	2.54	0.0100	mmhos/cm	1	BHI0616	09/18/24	09/19/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.58		pH Units	1	BHI0617	09/18/24	09/19/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
Project Manager: Paul Henchan

Reported:
09/23/24 08:40

BKG4 2FT
2409199-04 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Boron	ND	2.00	mg/L	1	BHI0492	09/16/24	09/17/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Arsenic	0.684	0.200	mg/kg dry	1	BHI0483	09/16/24	09/18/24	EPA 6020B	
Barium	82.3	0.400	"	"	"	"	"	"	
Cadmium	ND	0.200	"	"	"	"	"	"	
Copper	1.30	0.400	"	"	"	"	"	"	
Lead	6.62	0.200	"	"	"	"	"	"	
Nickel	1.77	0.400	"	"	"	"	"	"	
Silver	0.0377	0.0200	"	"	"	"	"	"	
Zinc	8.02	0.400	"	"	"	"	"	"	
Selenium	ND	0.260	"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Chromium, Hexavalent	ND	0.30	mg/kg dry	1	BHI0541	09/17/24	09/17/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Calcium	169	0.0500	mg/L dry	1	BHI0565	09/17/24	09/19/24	EPA 6020B	
Magnesium	34.3	0.0500	"	"	"	"	"	"	
Sodium	18.6	0.0500	"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

BKG4 2FT
2409199-04 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	0.341	0.00100	units	1	BHI0688	09/20/24	09/20/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	92.3		%	1	BHI0497	09/16/24	09/18/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.137	0.0100	mmhos/cm	1	BHI0616	09/18/24	09/19/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.58		pH Units	1	BHI0617	09/18/24	09/19/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
Project Manager: Paul Henchan

Reported:
09/23/24 08:40

BKG5 2FT
2409199-05 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Boron	ND	2.00	mg/L	1	BHI0492	09/16/24	09/17/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Arsenic	0.610	0.200	mg/kg dry	1	BHI0483	09/16/24	09/18/24	EPA 6020B	
Barium	39.8	0.400	"	"	"	"	"	"	
Cadmium	ND	0.200	"	"	"	"	"	"	
Copper	1.43	0.400	"	"	"	"	"	"	
Lead	5.83	0.200	"	"	"	"	"	"	
Nickel	1.35	0.400	"	"	"	"	"	"	
Silver	ND	0.0200	"	"	"	"	"	"	
Zinc	6.92	0.400	"	"	"	"	"	"	
Selenium	ND	0.260	"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Chromium, Hexavalent	ND	0.30	mg/kg dry	1	BHI0541	09/17/24	09/17/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Calcium	51.0	0.0500	mg/L dry	1	BHI0565	09/17/24	09/19/24	EPA 6020B	
Magnesium	12.8	0.0500	"	"	"	"	"	"	
Sodium	4.95	0.0500	"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
Project Manager: Paul Henchan

Reported:
09/23/24 08:40

BKG5 2FT
2409199-05 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	0.161	0.00100	units	1	BHI0688	09/20/24	09/20/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	96.7		%	1	BHI0497	09/16/24	09/18/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.475	0.0100	mmhos/cm	1	BHI0616	09/18/24	09/19/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **09/10/24 00:00**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	6.13		pH Units	1	BHI0617	09/18/24	09/19/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

Total Metals by EPA 6020B Hot Water Soluble Extraction - Quality Control

Summit Scientific

Analyte	Result	Reporting		Spike Level	Source Result	%REC		RPD		Notes
		Limit	Units			%REC	Limits	RPD	Limit	

Batch BHI0492 - EPA 3050B

Blank (BHI0492-BLK1)

Prepared: 09/16/24 Analyzed: 09/17/24

Boron ND 2.00 mg/L

LCS (BHI0492-BS1)

Prepared: 09/16/24 Analyzed: 09/18/24

Boron 5.40 2.00 mg/L 5.00 108 80-120

Duplicate (BHI0492-DUP1)

Source: 2409173-01

Prepared: 09/16/24 Analyzed: 09/17/24

Boron 0.474 2.00 mg/L 0.497 4.86 20

Matrix Spike (BHI0492-MS1)

Source: 2409173-01

Prepared: 09/16/24 Analyzed: 09/17/24

Boron 5.57 2.00 mg/L 5.02 0.497 101 75-125

Matrix Spike Dup (BHI0492-MSD1)

Source: 2409173-01

Prepared: 09/16/24 Analyzed: 09/17/24

Boron 5.45 2.00 mg/L 5.02 0.497 98.7 75-125 2.10 25

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
Project Manager: Paul Henchan

Reported:
09/23/24 08:40

Total Metals by EPA 6020B - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source	%REC		RPD		Notes
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	

Batch BHI0483 - EPA 3050B

Blank (BHI0483-BLK1)

Prepared: 09/16/24 Analyzed: 09/18/24

Arsenic	ND	0.200	mg/kg wet							
Barium	ND	0.400	"							
Cadmium	ND	0.200	"							
Copper	ND	0.400	"							
Lead	ND	0.200	"							
Nickel	ND	0.400	"							
Silver	ND	0.0200	"							
Zinc	ND	0.400	"							
Selenium	ND	0.260	"							

LCS (BHI0483-BS1)

Prepared: 09/16/24 Analyzed: 09/19/24

Arsenic	39.2	0.200	mg/kg wet	37.9	103	80-120				
Barium	38.5	0.400	"	37.9	102	80-120				
Cadmium	1.90	0.200	"	1.89	100	80-120				
Copper	39.1	0.400	"	37.9	103	80-120				
Lead	19.7	0.200	"	18.9	104	80-120				
Nickel	38.8	0.400	"	37.9	103	80-120				
Silver	1.95	0.0200	"	1.89	103	80-120				
Zinc	39.0	0.400	"	37.9	103	80-120				
Selenium	3.66	0.260	"	3.79	96.5	80-120				

Duplicate (BHI0483-DUP1)

Source: 2409193-01

Prepared: 09/16/24 Analyzed: 09/18/24

Arsenic	0.838	0.200	mg/kg dry	0.728			14.1	20		
Barium	26.2	0.400	"	21.4			19.9	20		
Cadmium	0.0147	0.200	"	0.0192			26.2	20		QR-01
Copper	1.27	0.400	"	1.49			16.4	20		
Lead	4.07	0.200	"	5.28			25.9	20		QR-04
Nickel	1.68	0.400	"	1.90			12.1	20		
Silver	0.421	0.0200	"	0.552			27.0	20		QR-04
Zinc	10.3	0.400	"	10.2			0.188	20		
Selenium	ND	0.260	"	ND				20		

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

Total Metals by EPA 6020B - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source		%REC		RPD		Notes
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit		

Batch BHI0483 - EPA 3050B

Matrix Spike (BHI0483-MS1)	Source: 2409193-01			Prepared: 09/16/24		Analyzed: 09/18/24					
Arsenic	18.0	0.200	mg/kg dry	46.4	0.728	37.3	75-125				QM-05
Barium	76.9	0.400	"	46.4	21.4	120	75-125				
Cadmium	2.20	0.200	"	2.32	0.0192	94.0	75-125				
Copper	18.7	0.400	"	46.4	1.49	37.1	75-125				QM-05
Lead	26.1	0.200	"	23.2	5.28	89.5	75-125				
Nickel	19.0	0.400	"	46.4	1.90	36.9	75-125				QM-05
Silver	2.53	0.0200	"	2.32	0.552	85.4	75-125				
Zinc	25.5	0.400	"	46.4	10.2	32.8	75-125				QM-05
Selenium	4.94	0.260	"	4.64	ND	106	75-125				

Matrix Spike Dup (BHI0483-MSD1)	Source: 2409193-01			Prepared: 09/16/24		Analyzed: 09/18/24					
Arsenic	19.4	0.200	mg/kg dry	46.8	0.728	39.9	75-125	7.36	25		QM-05
Barium	69.2	0.400	"	46.8	21.4	102	75-125	10.5	25		
Cadmium	2.33	0.200	"	2.34	0.0192	98.7	75-125	5.62	25		
Copper	20.0	0.400	"	46.8	1.49	39.6	75-125	6.62	25		QM-05
Lead	26.9	0.200	"	23.4	5.28	92.4	75-125	3.16	25		
Nickel	20.3	0.400	"	46.8	1.90	39.4	75-125	6.62	25		QM-05
Silver	2.61	0.0200	"	2.34	0.552	88.0	75-125	2.98	25		
Zinc	27.6	0.400	"	46.8	10.2	37.0	75-125	7.95	25		QM-05
Selenium	5.12	0.260	"	4.68	ND	110	75-125	3.70	25		

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

Hexavalent Chromium by EPA Method 7196 - Quality Control
Summit Scientific

Analyte	Result	Reporting		Spike Level	Source		%REC		RPD		Notes
		Limit	Units		Result	%REC	Limits	RPD	Limit		

Batch BHI0541 - 3060A Mod

Blank (BHI0541-BLK1)

Prepared & Analyzed: 09/17/24

Chromium, Hexavalent ND 0.30 mg/kg wet

LCS (BHI0541-BS1)

Prepared & Analyzed: 09/17/24

Chromium, Hexavalent 26.8 0.30 mg/kg wet 25.0 107 80-120

Duplicate (BHI0541-DUP1)

Source: 2409193-01

Prepared & Analyzed: 09/17/24

Chromium, Hexavalent ND 0.30 mg/kg dry ND 20

Matrix Spike (BHI0541-MS1)

Source: 2409193-01

Prepared & Analyzed: 09/17/24

Chromium, Hexavalent 30.6 0.30 mg/kg dry 29.7 ND 103 75-125

Matrix Spike Dup (BHI0541-MSD1)

Source: 2409193-01

Prepared & Analyzed: 09/17/24

Chromium, Hexavalent 30.4 0.30 mg/kg dry 29.7 ND 102 75-125 0.584 20

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction - Quality Control

Summit Scientific

Analyte	Result	Reporting		Spike Level	Source Result	%REC		RPD		Notes
		Limit	Units			%REC	Limits	RPD	Limit	

Batch BHI0565 - General Preparation

Blank (BHI0565-BLK1)

Prepared: 09/17/24 Analyzed: 09/19/24

Calcium	ND	0.0500	mg/L wet							
Magnesium	ND	0.0500	"							
Sodium	ND	0.0500	"							

LCS (BHI0565-BS1)

Prepared: 09/17/24 Analyzed: 09/19/24

Calcium	5.77	0.0500	mg/L wet	5.00	115	70-130				
Magnesium	5.15	0.0500	"	5.00	103	70-130				
Sodium	5.22	0.0500	"	5.00	104	70-130				

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

Physical Parameters by APHA/ASTM/EPA Methods - Quality Control

Summit Scientific

Analyte	Result	Reporting		Spike	Source		%REC		RPD		Notes
		Limit	Units	Level	Result	%REC	Limits	RPD	Limit		

Batch BHI0497 - General Preparation

Duplicate (BHI0497-DUP1)

Source: 2409194-01

Prepared: 09/16/24 Analyzed: 09/18/24

% Solids	91.9		%		91.3			0.758		20	
----------	------	--	---	--	------	--	--	-------	--	----	--

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction - Quality Control

Summit Scientific

Analyte	Result	Reporting		Spike Level	Source		%REC		RPD		Notes
		Limit	Units		Result	%REC	Limits	RPD	Limit		

Batch BHI0616 - General Preparation

Blank (BHI0616-BLK1)

Prepared: 09/18/24 Analyzed: 09/19/24

Specific Conductance (EC) ND 0.0100 mmhos/cm

LCS (BHI0616-BS1)

Prepared: 09/18/24 Analyzed: 09/19/24

Specific Conductance (EC) 0.153 0.0100 mmhos/cm 0.150 102 95-105

Duplicate (BHI0616-DUP1)

Source: 2409199-01

Prepared: 09/18/24 Analyzed: 09/19/24

Specific Conductance (EC) 0.120 0.0100 mmhos/cm 0.120 0.00 20

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
 Project Manager: Paul Henchan

Reported:
 09/23/24 08:40

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction - Quality Control

Summit Scientific

Analyte	Result	Reporting		Spike	Source	%REC		RPD		Notes
		Limit	Units	Level	Result	%REC	Limits	RPD	Limit	

Batch BHI0617 - General Preparation

LCS (BHI0617-BS1)

Prepared: 09/18/24 Analyzed: 09/19/24

pH	9.11	pH Units	9.18	99.2	95-105
----	------	----------	------	------	--------

Duplicate (BHI0617-DUP1)

Source: 2409199-01

Prepared: 09/18/24 Analyzed: 09/19/24

pH	8.43	pH Units	8.47	0.473	20
----	------	----------	------	-------	----

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Noble - Ocoma C17-15/TB (Background)

Project Number: UWRWE-A2638-ABN
Project Manager: Paul Henchan

Reported:
09/23/24 08:40

Notes and Definitions

- QR-04 The RPD value for the sample duplicate or MS/MSD was outside of QC acceptance limits. Sample results were accepted based on LCS and/or LCSD recoveries and/or RPD values.
- QR-01 Analyses are not controlled on RPD values from sample concentrations below the reporting limit. Sample results were accepted based on LCS and/or LCSD recoveries and/or RPD values.
- QM-05 The spike recovery was outside acceptance limits for the MS and/or MSD due to matrix interference. Sample results were accepted based on LCS and/or LCSD recoveries and/or RPD values.
- DET Analyte DETECTED
- ND Analyte NOT DETECTED at or above the reporting limit
- NR Not Reported
- dry Sample results reported on a dry weight basis
- RPD Relative Percent Difference