

# Summit Scientific

---

4653 Table Mountain Drive, Golden, Colorado 80403

303.277.9310

November 18, 2024

Paul Henchan  
Fremont Environmental  
PO Box 1289  
Wellington, CO 80549

RE: Chevron - Branch 1-3 (Facility and Flowline)

Work Order #2411129

Enclosed are the results of analyses for samples received by Summit Scientific on 11/07/24 16:30. If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Natalie Tessier For Paul Shrewsbury  
President



Fremont Environmental  
PO Box 1289  
Wellington CO, 80549

Project: Chevron - Branch 1-3 (Facility and Flowline)

Project Number: C022-187  
Project Manager: Paul Henchan

**Reported:**  
11/18/24 08:54

**ANALYTICAL REPORT FOR SAMPLES**

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
MW-1	2411129-01	Water	11/06/24 00:00	11/07/24 16:30
MW-2	2411129-02	Water	11/06/24 00:00	11/07/24 16:30
MW-3	2411129-03	Water	11/06/24 00:00	11/07/24 16:30
MW-4	2411129-04	Water	11/06/24 00:00	11/07/24 16:30
MW-5	2411129-05	Water	11/06/24 00:00	11/07/24 16:30

Client: Fremont Environmental	Send Data To: Project Manager: <u>Paul Henehan</u>	Send Invoice To: Company: <u>Noble (Chevron)</u>
Address: 8305 6th St.	E-Mail: <u>Chevron Dist. List, PDC Dist List, Civitas Dist List, Fremont Dist List</u> (paulH)mikeG,	Project Name/Location:
City/State/Zip: Wellington, CO	nickL (ethanB) jeffG, chrisL, stanG, aaronO, joshB (jordanS) tammyA (@fremontenv.com)	AFE#:
Phone: <u>864-423-2068</u>	Project Name: <u>Branch 1-3 (Facility and flowline)</u>	PO/Billing Codes:
Sampler Name: <u>Jordan Suttles</u>	Project Number: <u>6022-187</u>	Contact: <u>Dan Peterson</u>

Sample Description	Date Sampled	Time Sampled	Preservative					Matrix					Analysis Requested				Special Instructions	
			# of containers	HCl	HNO3	None	Other	Water	Soil	Air-Canister #	Other	Full Table 915-1 (Soil)	Full Table 915-1 (GW)					
MW-1	11/6/24		5	X														
MW-2									X						X			
MW-3																		
MW-4																		
MW-5																		

Relinquished by: <u>Jordan Suttles</u>	Date/Time: <u>18:03 11/6/24</u>	Received by: <u>S2-North Office</u>	Date/Time: <u>18:03 11/6/24</u>	TAT Business Days	Field DO	Notes: Dist. Report to parties circled in the email line(s) only.
Relinquished by: <u>S2</u>	Date/Time: <u>11724 1430</u>	Received by: <u>[Signature]</u>	Date/Time: <u>11724 1630</u>	Same Day	Field EC	
Relinquished by:	Date/Time:	Received by:	Date/Time:	1 Day	Field ORP	
				2 Days	Field pH	
				3 Days	Field Temp.	
				Standard	X Field Turb.	
Temperature Upon Receipt: <u>42</u>	Corrected Temperature: <u>0</u>	IR gun #:	HNO3 lot #:			

S<sub>2</sub>

Sample Receipt Checklist

S2 Work Order# 241129

Client: Fremont Client Project ID: Branch 1-3 (Facility/Flow/MU)

Shipped Via: H.D./P.U./FedEx/UPS/USPS/Other  Airbill #: \_\_\_\_\_

Matrix (Check all that apply) Air  Soil/Solid  Water  Other

Temp (°C) 4.2 Thermometer # 1

	Yes	No	N/A	Comments (if any)
If samples require cooling, is the temperature < 6°C? <sup>(1)</sup> NOTE: If samples are delivered the same day of sampling, this requirement is met if there is evidence that cooling has begun.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<u>on 20E</u>
If custody seals are present, are they intact? <sup>(1)</sup>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Are samples due within 48 hours present?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Are water samples with short hold times present? Note the short hold analysis in the comments column - pH, Nitrate/Nitrite, Ferrous Iron (Fe <sup>2+</sup> ), Hexavalent Chromium (Cr <sup>6+</sup> , Cr VI), COD/BOD, Total Coliform, E. Coli, Total Residual Chlorine (TRC), Dissolved Oxygen	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Is a chain-of-custody (COC) form present and filled out Completely? <sup>(1)</sup>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Is the COC properly relinquished by the client w/ date and time recorded? <sup>(1)</sup>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Were all samples received intact? <sup>(1)</sup>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Was adequate sample volume provided? <sup>(1)</sup>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Does the COC agree with the number and type of sample bottles received? <sup>(1)</sup>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Do the sample IDs on the bottle labels match the COC? <sup>(1)</sup>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
For volatiles in water – is there headspace present? If yes, contact client and note in narrative.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Are samples preserved that require preservation (excluding cooling)? <sup>(1)</sup> Note the type of preservative in the comments column – HCl, H <sub>2</sub> SO <sub>4</sub> , NaOH, HNO <sub>3</sub> , etc.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<u>HCl</u>
If samples are acid preserved for metals, is the pH ≤ 2? <sup>(1)</sup> Record the pH in Comments.	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
If dissolved metals are requested, were samples field filtered?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

Additional Comments (if any):

<sup>(1)</sup> If NO, then contact the client before proceeding with analysis and note in case narrative.

AS  
Custodian Printed Name

11/2/24  
Date/Time



Fremont Environmental  
PO Box 1289  
Wellington CO, 80549

Project: Chevron - Branch 1-3 (Facility and Flowline)

Project Number: C022-187  
Project Manager: Paul Henchan

**Reported:**  
11/18/24 08:54

**MW-1**  
**2411129-01 (Water)**

**Summit Scientific**

**Volatile Organic Compounds by EPA Method 8260B**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Benzene	ND	1.0		ug/l	1	BHK0533	11/11/24	11/11/24	EPA 8260B	
Toluene	ND	1.0		"	"	"	"	"	"	
Ethylbenzene	ND	1.0		"	"	"	"	"	"	
Xylenes (total)	ND	2.0		"	"	"	"	"	"	
Naphthalene	ND	1.0		"	"	"	"	"	"	
1,2,4-Trimethylbenzene	ND	1.0		"	"	"	"	"	"	
1,3,5-Trimethylbenzene	ND	1.0		"	"	"	"	"	"	

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Surrogate: 1,2-Dichloroethane-d4	15.6	117 %		23-173		"	"	"	"	
Surrogate: Toluene-d8	13.2	99.1 %		20-170		"	"	"	"	
Surrogate: 4-Bromofluorobenzene	13.5	101 %		21-167		"	"	"	"	

**Anions by EPA Method 300.0**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chloride	1740	0.0600		mg/L	50	BHK0591	11/12/24	11/13/24	EPA 300.0	
Sulfate	2270	0.300		"	"	"	"	"	"	

**Total Dissolved Solids by SM2540C**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
<b>Total Dissolved Solids</b>	<b>7010</b>	10.0		mg/L	1	BHK0460	11/11/24	11/12/24	SM2540C	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental  
PO Box 1289  
Wellington CO, 80549

Project: Chevron - Branch 1-3 (Facility and Flowline)

Project Number: C022-187  
Project Manager: Paul Henchan

**Reported:**  
11/18/24 08:54

**MW-2**  
**2411129-02 (Water)**

**Summit Scientific**

**Volatile Organic Compounds by EPA Method 8260B**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Benzene	ND	1.0		ug/l	1	BHK0533	11/11/24	11/11/24	EPA 8260B	
Toluene	ND	1.0		"	"	"	"	"	"	
Ethylbenzene	ND	1.0		"	"	"	"	"	"	
Xylenes (total)	ND	2.0		"	"	"	"	"	"	
Naphthalene	ND	1.0		"	"	"	"	"	"	
1,2,4-Trimethylbenzene	ND	1.0		"	"	"	"	"	"	
1,3,5-Trimethylbenzene	ND	1.0		"	"	"	"	"	"	

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Surrogate: 1,2-Dichloroethane-d4	15.2	114 %		23-173		"	"	"	"	
Surrogate: Toluene-d8	13.3	99.9 %		20-170		"	"	"	"	
Surrogate: 4-Bromofluorobenzene	13.2	99.2 %		21-167		"	"	"	"	

**Anions by EPA Method 300.0**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chloride	1880	0.0600		mg/L	50	BHK0591	11/12/24	11/13/24	EPA 300.0	
Sulfate	2560	0.300		"	"	"	"	"	"	

**Total Dissolved Solids by SM2540C**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Total Dissolved Solids	7750	10.0		mg/L	1	BHK0460	11/11/24	11/12/24	SM2540C	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental  
PO Box 1289  
Wellington CO, 80549

Project: Chevron - Branch 1-3 (Facility and Flowline)

Project Number: C022-187  
Project Manager: Paul Henchan

**Reported:**  
11/18/24 08:54

**MW-3**  
**2411129-03 (Water)**

**Summit Scientific**

**Volatile Organic Compounds by EPA Method 8260B**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Benzene	ND	1.0		ug/l	1	BHK0533	11/11/24	11/11/24	EPA 8260B	
Toluene	ND	1.0		"	"	"	"	"	"	
Ethylbenzene	ND	1.0		"	"	"	"	"	"	
Xylenes (total)	ND	2.0		"	"	"	"	"	"	
Naphthalene	ND	1.0		"	"	"	"	"	"	
1,2,4-Trimethylbenzene	ND	1.0		"	"	"	"	"	"	
1,3,5-Trimethylbenzene	ND	1.0		"	"	"	"	"	"	

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Surrogate: 1,2-Dichloroethane-d4	14.7	110 %		23-173		"	"	"	"	
Surrogate: Toluene-d8	13.2	98.9 %		20-170		"	"	"	"	
Surrogate: 4-Bromofluorobenzene	15.2	114 %		21-167		"	"	"	"	

**Anions by EPA Method 300.0**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chloride	1480	0.0600		mg/L	50	BHK0591	11/12/24	11/13/24	EPA 300.0	
Sulfate	2870	0.300		"	"	"	"	"	"	

**Total Dissolved Solids by SM2540C**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Total Dissolved Solids	7320	10.0		mg/L	1	BHK0460	11/11/24	11/12/24	SM2540C	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental  
PO Box 1289  
Wellington CO, 80549

Project: Chevron - Branch 1-3 (Facility and Flowline)

Project Number: C022-187  
Project Manager: Paul Henchan

**Reported:**  
11/18/24 08:54

**MW-4**  
**2411129-04 (Water)**

**Summit Scientific**

**Volatile Organic Compounds by EPA Method 8260B**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Benzene	ND	1.0		ug/l	1	BHK0533	11/11/24	11/12/24	EPA 8260B	
Toluene	ND	1.0		"	"	"	"	"	"	
Ethylbenzene	ND	1.0		"	"	"	"	"	"	
Xylenes (total)	ND	2.0		"	"	"	"	"	"	
Naphthalene	ND	1.0		"	"	"	"	"	"	
1,2,4-Trimethylbenzene	ND	1.0		"	"	"	"	"	"	
1,3,5-Trimethylbenzene	ND	1.0		"	"	"	"	"	"	

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Surrogate: 1,2-Dichloroethane-d4	15.4	115 %		23-173		"	"	"	"	
Surrogate: Toluene-d8	13.3	99.8 %		20-170		"	"	"	"	
Surrogate: 4-Bromofluorobenzene	13.4	100 %		21-167		"	"	"	"	

**Anions by EPA Method 300.0**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chloride	1890	0.0600		mg/L	50	BHK0591	11/12/24	11/13/24	EPA 300.0	
Sulfate	2320	0.300		"	"	"	"	"	"	

**Total Dissolved Solids by SM2540C**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Total Dissolved Solids	7610	10.0		mg/L	1	BHK0460	11/11/24	11/12/24	SM2540C	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental  
PO Box 1289  
Wellington CO, 80549

Project: Chevron - Branch 1-3 (Facility and Flowline)

Project Number: C022-187  
Project Manager: Paul Henchan

**Reported:**  
11/18/24 08:54

**MW-5**  
**2411129-05 (Water)**

**Summit Scientific**

**Volatile Organic Compounds by EPA Method 8260B**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Benzene	ND	1.0		ug/l	1	BHK0533	11/11/24	11/12/24	EPA 8260B	
Toluene	ND	1.0		"	"	"	"	"	"	
Ethylbenzene	ND	1.0		"	"	"	"	"	"	
Xylenes (total)	ND	2.0		"	"	"	"	"	"	
Naphthalene	ND	1.0		"	"	"	"	"	"	
1,2,4-Trimethylbenzene	ND	1.0		"	"	"	"	"	"	
1,3,5-Trimethylbenzene	ND	1.0		"	"	"	"	"	"	

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Surrogate: 1,2-Dichloroethane-d4	14.6	109 %		23-173		"	"	"	"	
Surrogate: Toluene-d8	13.3	100 %		20-170		"	"	"	"	
Surrogate: 4-Bromofluorobenzene	13.2	99.2 %		21-167		"	"	"	"	

**Anions by EPA Method 300.0**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chloride	1530	0.0600		mg/L	50	BHK0591	11/12/24	11/13/24	EPA 300.0	
Sulfate	2060	0.300		"	"	"	"	"	"	

**Total Dissolved Solids by SM2540C**

Date Sampled: **11/06/24 00:00**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Total Dissolved Solids	6400	10.0		mg/L	1	BHK0460	11/11/24	11/12/24	SM2540C	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental  
PO Box 1289  
Wellington CO, 80549

Project: Chevron - Branch 1-3 (Facility and Flowline)

Project Number: C022-187  
Project Manager: Paul Henchan

**Reported:**  
11/18/24 08:54

### Volatile Organic Compounds by EPA Method 8260B - Quality Control

#### Summit Scientific

Analyte	Result	Reporting		Spike Level	Source		%REC		RPD		Notes
		Limit	Units		Result	%REC	Limits	RPD	Limit		

#### Batch BHK0533 - EPA 5030 Water MS

##### Blank (BHK0533-BLK1)

Prepared & Analyzed: 11/11/24

Benzene	ND	1.0	ug/l								
Toluene	ND	1.0	"								
Ethylbenzene	ND	1.0	"								
Xylenes (total)	ND	2.0	"								
Naphthalene	ND	1.0	"								
1,2,4-Trimethylbenzene	ND	1.0	"								
1,3,5-Trimethylbenzene	ND	1.0	"								
Surrogate: 1,2-Dichloroethane-d4	14.2		"	13.3		106		23-173			
Surrogate: Toluene-d8	13.5		"	13.3		101		20-170			
Surrogate: 4-Bromofluorobenzene	13.2		"	13.3		99.2		21-167			

##### LCS (BHK0533-BS1)

Prepared & Analyzed: 11/11/24

Benzene	33.5	1.0	ug/l	33.3		100		51-132			
Toluene	33.2	1.0	"	33.3		99.6		51-138			
Ethylbenzene	35.5	1.0	"	33.3		107		58-146			
m,p-Xylene	70.7	2.0	"	66.7		106		57-144			
o-Xylene	33.9	1.0	"	33.3		102		53-146			
Naphthalene	34.4	1.0	"	33.3		103		70-130			
1,2,4-Trimethylbenzene	34.9	1.0	"	33.3		105		70-130			
1,3,5-Trimethylbenzene	35.6	1.0	"	33.3		107		70-130			
Surrogate: 1,2-Dichloroethane-d4	14.2		"	13.3		106		23-173			
Surrogate: Toluene-d8	13.5		"	13.3		101		20-170			
Surrogate: 4-Bromofluorobenzene	13.2		"	13.3		98.9		21-167			

##### LCS Dup (BHK0533-BSD1)

Prepared & Analyzed: 11/11/24

Benzene	34.8	1.0	ug/l	33.3		104		51-132	3.89	20	
Toluene	34.6	1.0	"	33.3		104		51-138	3.99	20	
Ethylbenzene	37.9	1.0	"	33.3		114		58-146	6.59	20	
m,p-Xylene	74.9	2.0	"	66.7		112		57-144	5.81	20	
o-Xylene	36.0	1.0	"	33.3		108		53-146	5.92	20	
Naphthalene	36.6	1.0	"	33.3		110		70-130	6.22	20	
1,2,4-Trimethylbenzene	37.0	1.0	"	33.3		111		70-130	5.86	20	
1,3,5-Trimethylbenzene	37.9	1.0	"	33.3		114		70-130	6.21	20	
Surrogate: 1,2-Dichloroethane-d4	14.0		"	13.3		105		23-173			
Surrogate: Toluene-d8	13.6		"	13.3		102		20-170			
Surrogate: 4-Bromofluorobenzene	13.4		"	13.3		100		21-167			

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental  
 PO Box 1289  
 Wellington CO, 80549

Project: Chevron - Branch 1-3 (Facility and Flowline)

Project Number: C022-187  
 Project Manager: Paul Henchan

**Reported:**  
 11/18/24 08:54

**Anions by EPA Method 300.0 - Quality Control**

**Summit Scientific**

Analyte	Result	Reporting		Spike Level	Source		%REC		RPD		Notes
		Limit	Units		Result	%REC	Limits	RPD	Limit		

**Batch BHK0591 - General Preparation**

**Blank (BHK0591-BLK1)**

Prepared: 11/12/24 Analyzed: 11/13/24

Chloride	ND	0.0600	mg/L							
Sulfate	ND	0.300	"							

**LCS (BHK0591-BS1)**

Prepared: 11/12/24 Analyzed: 11/13/24

Chloride	3.10	0.0600	mg/L	3.00	103	90-110				
Sulfate	15.3	0.300	"	15.0	102	90-110				

**Duplicate (BHK0591-DUP1)**

Source: 2411127-01

Prepared: 11/12/24 Analyzed: 11/13/24

Chloride	191	0.0600	mg/L		194		1.60	20		
Sulfate	83.4	0.300	"		84.5		1.28	20		

**Matrix Spike (BHK0591-MS1)**

Source: 2411127-01

Prepared: 11/12/24 Analyzed: 11/13/24

Chloride	338	0.0600	mg/L	150	194	96.0	80-120			
Sulfate	825	0.300	"	750	84.5	98.8	80-120			

Summit Scientific

*The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.*



Fremont Environmental  
 PO Box 1289  
 Wellington CO, 80549

Project: Chevron - Branch 1-3 (Facility and Flowline)

Project Number: C022-187  
 Project Manager: Paul Henchan

**Reported:**  
 11/18/24 08:54

**Total Dissolved Solids by SM2540C - Quality Control**  
**Summit Scientific**

Analyte	Result	Reporting		Spike Level	Source		%REC		RPD		Notes
		Limit	Units		Result	%REC	Limits	RPD	Limit		

**Batch BHK0460 - General Preparation**

**Blank (BHK0460-BLK1)**

Prepared: 11/11/24 Analyzed: 11/12/24

Total Dissolved Solids      ND      10.0      mg/L

**Duplicate (BHK0460-DUP1)**

**Source: 2411128-01**

Prepared: 11/11/24 Analyzed: 11/12/24

Total Dissolved Solids      969      10.0      mg/L      925      4.65      20

Summit Scientific

*The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.*



Fremont Environmental  
PO Box 1289  
Wellington CO, 80549

Project: Chevron - Branch 1-3 (Facility and Flowline)

Project Number: C022-187  
Project Manager: Paul Henchan

**Reported:**  
11/18/24 08:54

### Notes and Definitions

DET Analyte DETECTED  
ND Analyte NOT DETECTED at or above the reporting limit  
NR Not Reported  
dry Sample results reported on a dry weight basis  
RPD Relative Percent Difference