

Summit Scientific

4653 Table Mountain Drive, Golden, Colorado 80403

303.277.9310


April 23, 2024

Paul Henchan
Fremont Environmental
PO Box 1289
Wellington, CO 80549

RE: Chevron - Howard USX A09-13 Flowline
Work Order #2403132

Enclosed are the results of analyses for samples received by Summit Scientific on 03/07/24 17:42. If you have any questions concerning this report, please feel free to contact me.

Sincerely,

A handwritten signature in blue ink that reads "Jacob Wood". The signature is written in a cursive style with a large initial "J" and a distinct "W".

Jacob Wood For Paul Shrewsbury
President



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
FL01 2FT	2403132-01	Soil	03/07/24 13:05	03/07/24 17:42
FL02 2FT	2403132-02	Soil	03/07/24 13:10	03/07/24 17:42
FL03 2FT	2403132-03	Soil	03/07/24 13:15	03/07/24 17:42
FL04 2FT	2403132-04	Soil	03/07/24 13:20	03/07/24 17:42
FL05 2FT	2403132-05	Soil	03/07/24 13:25	03/07/24 17:42
BKG04@0.5'	2403132-06	Soil	03/07/24 13:30	03/07/24 17:42
BKG04@2'	2403132-07	Soil	03/07/24 13:35	03/07/24 17:42
BKG04@5'	2403132-08	Soil	03/07/24 13:40	03/07/24 17:42
BKG05@0.5'	2403132-09	Soil	03/07/24 13:45	03/07/24 17:42
BKG05@2'	2403132-10	Soil	03/07/24 13:50	03/07/24 17:42
BKG05@5'	2403132-11	Soil	03/07/24 13:55	03/07/24 17:42

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

SUMMIT SCIENTIFIC

4653 Table Mountain Drive
Golden, CO 80403
303-277-9310

Lab ID 2403132 Page 1 of 1

Send Data To:		Send Invoice To:	
Client: Fremont Environmental	Project Manager: Paul Henehan	Company: <u>Chalon</u>	
Address: 8305 6th Street	E-Mail: Fremont Distribution List	Project Name/Location:	
City/State/Zip: Wellington, CO, 80549		AFE#: <u>OWRWE-A3602-ABN</u>	
Phone: 603-477-6907	Project Name: <u>Howard USX A09-13 Flowline</u>	PO/Billing Codes:	
Sampler Name: Aaron Otilar	Project Number:	Contact: <u>MIKE MONTOYA</u>	

ID	Sample Description	Date Sampled	Time Sampled	# of containers	Preservative				Matrix		Analysis Requested							Special Instructions	
					HCl	HNO3	None	Other	Water	Soil	Air-Canister #	Other	BTEXN - 915	TPH (C6-C36)	PAH	TMB's - 915	Metals (915-1)		SAR, EC, pH, Boron
1	FLO1 2Ft	3/7/24	1305	2			X			X			X	X	X	X	X		
2	FLO2 2Ft		1310										X	X	X	X	X		
3	FLO3 2Ft		1315										X	X	X	X	X		
4	FLO4 2Ft		1320										X	X	X	X	X		
5	FLO5 2Ft		1325										X	X	X	X	X		
6	BK04 eo.5'		1330	1											X	X			
7	BK04 02'		1335																
8	BK04 05'		1340																
9	BK05 eo.5'		1345																
10	BK05 02'		1350																
11	BK05 05'		1355																
12																			
13																			
14																			
15																			

Relinquished by: <u>Aaron Otilar</u>	Date/Time: <u>3/7/24 1620</u>	Received by: <u>Summit North Office</u>	Date/Time: <u>3/7/24 1620</u>	TAT Business Days	Field DO	Notes:
				Same Day	Field EC	
Relinquished by: <u>S2</u>	Date/Time: <u>3/24 1645</u>	Received by: <u>[Signature]</u>	Date/Time: <u>3/24 1645</u>	1 Day	Field ORP	
				2 Days	Field pH	
				3 Days	Field Temp.	
				Standard	X Field Turb.	
Temperature Upon Receipt: <u>11.1</u>	Corrected Temperature: <u>0</u>	IR gun #: <u>1</u>	HNO3 lot #: <u></u>			

S₂

Sample Receipt Checklist

S2 Work Order# 2403132

Client: Fremont Client Project ID: Howard USX Am-13 flowline

Shipped Via: H.D./P.U./FedEx/UPS/USPS/Other Airbill #: _____

Matrix (Check all that apply) Air Soil/Solid Water Other

Temp (°C) 11.1 Thermometer # 1

	Yes	No	N/A	Comments (if any)
If samples require cooling, is the temperature < 6°C? ⁽¹⁾ NOTE: If samples are delivered the same day of sampling, this requirement is met if there is evidence that cooling has begun.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
If custody seals are present, are they intact? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<u>awful</u>
Are samples due within 48 hours present?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Are water samples with short hold times present? Note the short hold analysis in the comments column - pH, Nitrate/Nitrite, Ferrous Iron (Fe ²⁺), Hexavalent Chromium (Cr ⁶⁺ , Cr VI), COD/BOD, Total Coliform, E. Coli, Total Residual Chlorine (TRC), Dissolved Oxygen	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Is a chain-of-custody (COC) form present and filled out Completely? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Is the COC properly relinquished by the client w/ date and time recorded? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Were all samples received intact? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Was adequate sample volume provided? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Does the COC agree with the number and type of sample bottles received? ⁽¹⁾	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Do the sample IDs on the bottle labels match the COC? ⁽¹⁾	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<u>no sample times, not all jars had "FL"</u>
For volatiles in water – is there headspace present? If yes, contact client and note in narrative.	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	"
Are samples preserved that require preservation (excluding cooling)? ⁽¹⁾ Note the type of preservative in the comments column – HCl, H ₂ SO ₄ , NaOH, HNO ₃ , etc.	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
If samples are acid preserved for metals, is the pH ≤ 2? ⁽¹⁾ Record the pH in Comments.	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
If dissolved metals are requested, were samples field filtered?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Additional Comments (if any):				

⁽¹⁾ If NO, then contact the client before proceeding with analysis and note in case narrative.

AS
Custodian Printed Name

3/7/24
Date/Time



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL01 2FT
2403132-01 (Soil)

Summit Scientific

Volatile Organic Compounds by EPA Method 8260B

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Benzene	ND	0.0020		mg/kg	1	BHC0279	03/11/24	03/12/24	EPA 8260B	
Toluene	ND	0.0050		"	"	"	"	"	"	
Ethylbenzene	ND	0.0050		"	"	"	"	"	"	
Xylenes (total)	ND	0.010		"	"	"	"	"	"	
1,2,4-Trimethylbenzene	ND	0.0050		"	"	"	"	"	"	
1,3,5-Trimethylbenzene	ND	0.0050		"	"	"	"	"	"	
Naphthalene	ND	0.0038		"	"	"	"	"	"	
Gasoline Range Hydrocarbons	ND	0.50		"	"	"	"	"	"	

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Surrogate: 1,2-Dichloroethane-d4	0.0318	79.5 %		50-150		"	"	"	"	
Surrogate: Toluene-d8	0.0407	102 %		50-150		"	"	"	"	
Surrogate: 4-Bromofluorobenzene	0.0392	98.0 %		50-150		"	"	"	"	

Extractable Petroleum Hydrocarbons by 8015

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
C10-C28 (DRO)	ND	50		mg/kg	1	BHC0282	03/11/24	03/12/24	EPA 8015M	
C28-C36 (ORO)	ND	50		"	"	"	"	"	"	

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Surrogate: o-Terphenyl	4.87	38.9 %		30-150		"	"	"	"	

PAH by EPA Method 8270D SIM

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL01 2FT
2403132-01 (Soil)

Summit Scientific

PAH by EPA Method 8270D SIM

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Acenaphthene	ND	0.00500	mg/kg	1	BHC0324	03/12/24	03/13/24	EPA 8270D SIM	
Anthracene	ND	0.00500	"	"	"	"	"	"	
Benzo (a) anthracene	ND	0.00500	"	"	"	"	"	"	
Benzo (a) pyrene	ND	0.00500	"	"	"	"	"	"	
Benzo (b) fluoranthene	ND	0.00500	"	"	"	"	"	"	
Benzo (k) fluoranthene	ND	0.00500	"	"	"	"	"	"	
Chrysene	ND	0.00500	"	"	"	"	"	"	
Dibenz (a,h) anthracene	ND	0.00500	"	"	"	"	"	"	
Fluoranthene	ND	0.00500	"	"	"	"	"	"	
Fluorene	ND	0.00500	"	"	"	"	"	"	
Indeno (1,2,3-cd) pyrene	ND	0.00500	"	"	"	"	"	"	
Pyrene	ND	0.00500	"	"	"	"	"	"	
1-Methylnaphthalene	ND	0.00500	"	"	"	"	"	"	
2-Methylnaphthalene	ND	0.00500	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: 2-Methylnaphthalene-d10	0.0169	50.7 %	40-150		"	"	"	"	
Surrogate: Fluoranthene-d10	0.0135	40.5 %	40-150		"	"	"	"	

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Boron	ND	2.00	mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
---------	--------	-----------------	-------	----------	-------	----------	----------	--------	-------

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL01 2FT
2403132-01 (Soil)

Summit Scientific

Total Metals by EPA 6020B

Analyte	Result	Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Arsenic	15.3	0.200	mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B	
Barium	55.9	0.400	"	"	"	"	"	"	
Cadmium	ND	0.200	"	"	"	"	"	"	
Copper	4.90	0.400	"	"	"	"	"	"	
Lead	10.1	0.200	"	"	"	"	"	"	
Nickel	4.16	0.400	"	"	"	"	"	"	
Silver	0.0269	0.0200	"	"	"	"	"	"	
Zinc	24.5	0.400	"	"	"	"	"	"	
Selenium	ND	0.260	"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Chromium, Hexavalent	ND	0.30	mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Calcium	38.8	0.0500	mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	7.18	0.0500	"	"	"	"	"	"	
Sodium	15.7	0.0500	"	"	"	"	"	"	

Calculated Analysis

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	0.608	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

FL01 2FT
2403132-01 (Soil)

Summit Scientific

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	89.2		%	1	BHC0432	03/15/24	03/16/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.818	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:05**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.45		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL02 2FT
2403132-02 (Soil)

Summit Scientific

Volatile Organic Compounds by EPA Method 8260B

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Benzene	ND	0.0020	mg/kg	1	BHC0279	03/11/24	03/12/24	EPA 8260B	
Toluene	ND	0.0050	"	"	"	"	"	"	
Ethylbenzene	ND	0.0050	"	"	"	"	"	"	
Xylenes (total)	ND	0.010	"	"	"	"	"	"	
1,2,4-Trimethylbenzene	ND	0.0050	"	"	"	"	"	"	
1,3,5-Trimethylbenzene	ND	0.0050	"	"	"	"	"	"	
Naphthalene	0.021	0.0038	"	"	"	"	"	"	
Gasoline Range Hydrocarbons	ND	0.50	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: 1,2-Dichloroethane-d4	0.0314	78.5 %	50-150		"	"	"	"	
Surrogate: Toluene-d8	0.0400	100 %	50-150		"	"	"	"	
Surrogate: 4-Bromofluorobenzene	0.0417	104 %	50-150		"	"	"	"	

Extractable Petroleum Hydrocarbons by 8015

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
C10-C28 (DRO)	ND	50	mg/kg	1	BHC0282	03/11/24	03/12/24	EPA 8015M	
C28-C36 (ORO)	ND	50	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: o-Terphenyl	4.54	36.3 %	30-150		"	"	"	"	

PAH by EPA Method 8270D SIM

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL02 2FT
2403132-02 (Soil)

Summit Scientific

PAH by EPA Method 8270D SIM

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Acenaphthene	0.0151	0.00500	mg/kg	1	BHC0324	03/12/24	03/13/24	EPA 8270D SIM	
Anthracene	0.0198	0.00500	"	"	"	"	"	"	
Benzo (a) anthracene	0.0269	0.00500	"	"	"	"	"	"	
Benzo (a) pyrene	0.0160	0.00500	"	"	"	"	"	"	
Benzo (b) fluoranthene	0.0211	0.00500	"	"	"	"	"	"	
Benzo (k) fluoranthene	0.00764	0.00500	"	"	"	"	"	"	
Chrysene	0.0237	0.00500	"	"	"	"	"	"	
Dibenz (a,h) anthracene	ND	0.00500	"	"	"	"	"	"	
Fluoranthene	0.0678	0.00500	"	"	"	"	"	"	
Fluorene	0.0166	0.00500	"	"	"	"	"	"	
Indeno (1,2,3-cd) pyrene	0.0304	0.00500	"	"	"	"	"	"	
Pyrene	0.101	0.00500	"	"	"	"	"	"	
1-Methylnaphthalene	ND	0.00500	"	"	"	"	"	"	
2-Methylnaphthalene	ND	0.00500	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: 2-Methylnaphthalene-d10	0.0155	46.4 %	40-150		"	"	"	"	
Surrogate: Fluoranthene-d10	0.0150	44.9 %	40-150		"	"	"	"	

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Boron	ND	2.00	mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Arsenic	23.0	0.200	mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL02 2FT
2403132-02 (Soil)

Summit Scientific

Total Metals by EPA 6020B

Analyte	Result	Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Barium	45.7	0.400	mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B	
Cadmium	ND	0.200	"	"	"	"	"	"	
Copper	4.51	0.400	"	"	"	"	"	"	
Lead	7.83	0.200	"	"	"	"	"	"	
Nickel	3.04	0.400	"	"	"	"	"	"	
Silver	0.0224	0.0200	"	"	"	"	"	"	
Zinc	21.4	0.400	"	"	"	"	"	"	
Selenium	ND	0.260	"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Chromium, Hexavalent	ND	0.30	mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Calcium	52.3	0.0500	mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	37.9	0.0500	"	"	"	"	"	"	
Sodium	77.2	0.0500	"	"	"	"	"	"	

Calculated Analysis

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	1.98	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
---------	--------	-----------------	-------	----------	-------	----------	----------	--------	-------

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

FL02 2FT
2403132-02 (Soil)

Summit Scientific

Physical Parameters by APHA/ASTM/EPA Methods

% Solids	89.1	%	1	BHC0432	03/15/24	03/16/24	Calculation
----------	------	---	---	---------	----------	----------	-------------

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:10**


Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	3.02	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:10**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.39		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific



The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL03 2FT
2403132-03 (Soil)

Summit Scientific

Volatile Organic Compounds by EPA Method 8260B

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Benzene	ND	0.0020		mg/kg	1	BHC0279	03/11/24	03/12/24	EPA 8260B	
Toluene	ND	0.0050		"	"	"	"	"	"	
Ethylbenzene	ND	0.0050		"	"	"	"	"	"	
Xylenes (total)	ND	0.010		"	"	"	"	"	"	
1,2,4-Trimethylbenzene	ND	0.0050		"	"	"	"	"	"	
1,3,5-Trimethylbenzene	ND	0.0050		"	"	"	"	"	"	
Naphthalene	ND	0.0038		"	"	"	"	"	"	
Gasoline Range Hydrocarbons	ND	0.50		"	"	"	"	"	"	

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Surrogate: 1,2-Dichloroethane-d4	0.0338	84.5 %		50-150		"	"	"	"	
Surrogate: Toluene-d8	0.0400	100 %		50-150		"	"	"	"	
Surrogate: 4-Bromofluorobenzene	0.0393	98.2 %		50-150		"	"	"	"	

Extractable Petroleum Hydrocarbons by 8015

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
C10-C28 (DRO)	ND	50		mg/kg	1	BHC0282	03/11/24	03/12/24	EPA 8015M	
C28-C36 (ORO)	ND	50		"	"	"	"	"	"	

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Surrogate: o-Terphenyl	5.26	42.1 %		30-150		"	"	"	"	

PAH by EPA Method 8270D SIM

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

FL03 2FT
2403132-03 (Soil)

Summit Scientific

PAH by EPA Method 8270D SIM

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Acenaphthene	ND	0.00500	mg/kg	1	BHC0324	03/12/24	03/13/24	EPA 8270D SIM	
Anthracene	ND	0.00500	"	"	"	"	"	"	
Benzo (a) anthracene	ND	0.00500	"	"	"	"	"	"	
Benzo (a) pyrene	ND	0.00500	"	"	"	"	"	"	
Benzo (b) fluoranthene	ND	0.00500	"	"	"	"	"	"	
Benzo (k) fluoranthene	ND	0.00500	"	"	"	"	"	"	
Chrysene	ND	0.00500	"	"	"	"	"	"	
Dibenz (a,h) anthracene	ND	0.00500	"	"	"	"	"	"	
Fluoranthene	ND	0.00500	"	"	"	"	"	"	
Fluorene	ND	0.00500	"	"	"	"	"	"	
Indeno (1,2,3-cd) pyrene	ND	0.00500	"	"	"	"	"	"	
Pyrene	ND	0.00500	"	"	"	"	"	"	
1-Methylnaphthalene	ND	0.00500	"	"	"	"	"	"	
2-Methylnaphthalene	ND	0.00500	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: 2-Methylnaphthalene-d10	0.0211	63.2 %	40-150		"	"	"	"	
Surrogate: Fluoranthene-d10	0.0143	42.9 %	40-150		"	"	"	"	

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Boron	ND	2.00	mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
---------	--------	-----------------	-------	----------	-------	----------	----------	--------	-------

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL03 2FT
2403132-03 (Soil)

Summit Scientific

Total Metals by EPA 6020B

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Arsenic	7.65	0.200	mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B	
Barium	63.5	0.400	"	"	"	"	"	"	
Cadmium	0.319	0.200	"	"	"	"	"	"	
Copper	10.3	0.400	"	"	"	"	"	"	
Lead	19.2	0.200	"	"	"	"	"	"	
Nickel	4.81	0.400	"	"	"	"	"	"	
Silver	0.0828	0.0200	"	"	"	"	"	"	
Zinc	30.5	0.400	"	"	"	"	"	"	
Selenium	0.305	0.260	"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Chromium, Hexavalent	ND	0.30	mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Calcium	79.3	0.0500	mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	168	0.0500	"	"	"	"	"	"	
Sodium	473	0.0500	"	"	"	"	"	"	

Calculated Analysis

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	6.90	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
---------	--------	-----------------	-------	----------	-------	----------	----------	--------	-------

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

FL03 2FT
2403132-03 (Soil)

Summit Scientific

Physical Parameters by APHA/ASTM/EPA Methods

% Solids	88.4	%	1	BHC0432	03/15/24	03/16/24	Calculation
----------	------	---	---	---------	----------	----------	-------------

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:15**


Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	1.12	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:15**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.46		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific



The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL04 2FT
2403132-04 (Soil)

Summit Scientific

Volatile Organic Compounds by EPA Method 8260B

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Benzene	ND	0.0020	mg/kg	1	BHC0279	03/11/24	03/12/24	EPA 8260B	
Toluene	ND	0.0050	"	"	"	"	"	"	
Ethylbenzene	ND	0.0050	"	"	"	"	"	"	
Xylenes (total)	ND	0.010	"	"	"	"	"	"	
1,2,4-Trimethylbenzene	ND	0.0050	"	"	"	"	"	"	
1,3,5-Trimethylbenzene	ND	0.0050	"	"	"	"	"	"	
Naphthalene	ND	0.0038	"	"	"	"	"	"	
Gasoline Range Hydrocarbons	ND	0.50	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Surrogate: 1,2-Dichloroethane-d4	0.0318	79.5 %	50-150	"	"	"	"	"	
Surrogate: Toluene-d8	0.0408	102 %	50-150	"	"	"	"	"	
Surrogate: 4-Bromofluorobenzene	0.0403	101 %	50-150	"	"	"	"	"	

Extractable Petroleum Hydrocarbons by 8015

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
C10-C28 (DRO)	ND	50	mg/kg	1	BHC0282	03/11/24	03/12/24	EPA 8015M	
C28-C36 (ORO)	ND	50	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Surrogate: o-Terphenyl	4.54	36.3 %	30-150	"	"	"	"	"	

PAH by EPA Method 8270D SIM

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

FL04 2FT
2403132-04 (Soil)

Summit Scientific

PAH by EPA Method 8270D SIM

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Acenaphthene	ND	0.00500	mg/kg	1	BHC0324	03/12/24	03/13/24	EPA 8270D SIM	
Anthracene	ND	0.00500	"	"	"	"	"	"	
Benzo (a) anthracene	ND	0.00500	"	"	"	"	"	"	
Benzo (a) pyrene	ND	0.00500	"	"	"	"	"	"	
Benzo (b) fluoranthene	ND	0.00500	"	"	"	"	"	"	
Benzo (k) fluoranthene	ND	0.00500	"	"	"	"	"	"	
Chrysene	ND	0.00500	"	"	"	"	"	"	
Dibenz (a,h) anthracene	ND	0.00500	"	"	"	"	"	"	
Fluoranthene	0.00755	0.00500	"	"	"	"	"	"	
Fluorene	ND	0.00500	"	"	"	"	"	"	
Indeno (1,2,3-cd) pyrene	ND	0.00500	"	"	"	"	"	"	
Pyrene	0.0149	0.00500	"	"	"	"	"	"	
1-Methylnaphthalene	ND	0.00500	"	"	"	"	"	"	
2-Methylnaphthalene	ND	0.00500	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: 2-Methylnaphthalene-d10	0.0218	65.5 %	40-150		"	"	"	"	
Surrogate: Fluoranthene-d10	0.0148	44.3 %	40-150		"	"	"	"	

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Boron	ND	2.00	mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
---------	--------	-----------------	-------	----------	-------	----------	----------	--------	-------

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL04 2FT
2403132-04 (Soil)

Summit Scientific

Total Metals by EPA 6020B

Analyte	Result	Limit	Units	Dilution	Batch	Prepared	Analyzed	Method
Arsenic	3.35	0.200	mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B
Barium	60.6	0.400	"	"	"	"	"	"
Cadmium	0.259	0.200	"	"	"	"	"	"
Copper	6.15	0.400	"	"	"	"	"	"
Lead	11.5	0.200	"	"	"	"	"	"
Nickel	6.36	0.400	"	"	"	"	"	"
Silver	0.0328	0.0200	"	"	"	"	"	"
Zinc	29.8	0.400	"	"	"	"	"	"
Selenium	ND	0.260	"	"	"	"	"	"

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Chromium, Hexavalent	ND	0.30	mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Calcium	84.6	0.0500	mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	59.3	0.0500	"	"	"	"	"	"	
Sodium	87.0	0.0500	"	"	"	"	"	"	

Calculated Analysis

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	1.77	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
---------	--------	-----------------	-------	----------	-------	----------	----------	--------	-------

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

FL04 2FT
2403132-04 (Soil)

Summit Scientific

Physical Parameters by APHA/ASTM/EPA Methods

% Solids	92.7	%	1	BHC0432	03/15/24	03/16/24	Calculation
----------	------	---	---	---------	----------	----------	-------------

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:20**


Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.206	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:20**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.10		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific



The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

FL05 2FT
2403132-05 (Soil)

Summit Scientific

Volatile Organic Compounds by EPA Method 8260B

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Benzene	ND	0.0020	mg/kg	1	BHC0279	03/11/24	03/12/24	EPA 8260B	
Toluene	ND	0.0050	"	"	"	"	"	"	
Ethylbenzene	ND	0.0050	"	"	"	"	"	"	
Xylenes (total)	ND	0.010	"	"	"	"	"	"	
1,2,4-Trimethylbenzene	ND	0.0050	"	"	"	"	"	"	
1,3,5-Trimethylbenzene	ND	0.0050	"	"	"	"	"	"	
Naphthalene	ND	0.0038	"	"	"	"	"	"	
Gasoline Range Hydrocarbons	ND	0.50	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Surrogate: 1,2-Dichloroethane-d4	0.0345	86.2 %	50-150	"	"	"	"	"	
Surrogate: Toluene-d8	0.0404	101 %	50-150	"	"	"	"	"	
Surrogate: 4-Bromofluorobenzene	0.0400	100 %	50-150	"	"	"	"	"	

Extractable Petroleum Hydrocarbons by 8015

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
C10-C28 (DRO)	ND	50	mg/kg	1	BHC0282	03/11/24	03/12/24	EPA 8015M	
C28-C36 (ORO)	ND	50	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Surrogate: o-Terphenyl	7.78	62.2 %	30-150	"	"	"	"	"	

PAH by EPA Method 8270D SIM

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL05 2FT
2403132-05 (Soil)

Summit Scientific

PAH by EPA Method 8270D SIM

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Acenaphthene	ND	0.00500	mg/kg	1	BHC0324	03/12/24	03/13/24	EPA 8270D SIM	
Anthracene	ND	0.00500	"	"	"	"	"	"	
Benzo (a) anthracene	ND	0.00500	"	"	"	"	"	"	
Benzo (a) pyrene	ND	0.00500	"	"	"	"	"	"	
Benzo (b) fluoranthene	ND	0.00500	"	"	"	"	"	"	
Benzo (k) fluoranthene	ND	0.00500	"	"	"	"	"	"	
Chrysene	ND	0.00500	"	"	"	"	"	"	
Dibenz (a,h) anthracene	ND	0.00500	"	"	"	"	"	"	
Fluoranthene	ND	0.00500	"	"	"	"	"	"	
Fluorene	ND	0.00500	"	"	"	"	"	"	
Indeno (1,2,3-cd) pyrene	ND	0.00500	"	"	"	"	"	"	
Pyrene	ND	0.00500	"	"	"	"	"	"	
1-Methylnaphthalene	ND	0.00500	"	"	"	"	"	"	
2-Methylnaphthalene	ND	0.00500	"	"	"	"	"	"	

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Surrogate: 2-Methylnaphthalene-d10	0.0199	59.7 %	40-150		"	"	"	"	
Surrogate: Fluoranthene-d10	0.0135	40.6 %	40-150		"	"	"	"	

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Boron	ND	2.00	mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
---------	--------	-----------------	-------	----------	-------	----------	----------	--------	-------

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

FL05 2FT
2403132-05 (Soil)

Summit Scientific

Total Metals by EPA 6020B

Analyte	Result	Limit	Units	Dilution	Batch	Prepared	Analyzed	Method
Arsenic	4.72	0.200	mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B
Barium	94.0	0.400	"	"	"	"	"	"
Cadmium	0.266	0.200	"	"	"	"	"	"
Copper	5.92	0.400	"	"	"	"	"	"
Lead	8.52	0.200	"	"	"	"	"	"
Nickel	6.69	0.400	"	"	"	"	"	"
Silver	0.0393	0.0200	"	"	"	"	"	"
Zinc	23.2	0.400	"	"	"	"	"	"
Selenium	ND	0.260	"	"	"	"	"	"

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Chromium, Hexavalent	ND	0.30	mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Calcium	52.1	0.0500	mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	9.80	0.0500	"	"	"	"	"	"	
Sodium	24.9	0.0500	"	"	"	"	"	"	

Calculated Analysis

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	0.830	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
---------	--------	-----------------	-------	----------	-------	----------	----------	--------	-------

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

FL05 2FT
2403132-05 (Soil)

Summit Scientific

Physical Parameters by APHA/ASTM/EPA Methods

% Solids	85.6	%	1	BHC0432	03/15/24	03/16/24	Calculation
----------	------	---	---	---------	----------	----------	-------------

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:25**


Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.603	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:25**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.70		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific



The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

BKG04@0.5'
2403132-06 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:30**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Boron	ND	2.00	mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:30**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Arsenic	6.48	0.200	mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B	
Barium	71.2	0.400	"	"	"	"	"	"	
Cadmium	0.308	0.200	"	"	"	"	"	"	
Copper	17.4	0.400	"	"	"	"	"	"	
Lead	11.5	0.200	"	"	"	"	"	"	
Nickel	6.80	0.400	"	"	"	"	"	"	
Silver	0.0526	0.0200	"	"	"	"	"	"	
Zinc	39.5	0.400	"	"	"	"	"	"	
Selenium	ND	0.260	"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:30**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Chromium, Hexavalent	ND	0.30	mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:30**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Calcium	75.1	0.0500	mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	16.8	0.0500	"	"	"	"	"	"	
Sodium	47.6	0.0500	"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

BKG04@0.5'
2403132-06 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **03/07/24 13:30**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	1.29	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:30**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	85.1		%	1	BHC0432	03/15/24	03/16/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:30**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.442	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:30**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.28		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

BKG04@2'
2403132-07 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:35**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Boron	ND	2.00		mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:35**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Arsenic	7.49	0.200		mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B	
Barium	31.0	0.400		"	"	"	"	"	"	
Cadmium	0.294	0.200		"	"	"	"	"	"	
Copper	6.62	0.400		"	"	"	"	"	"	
Lead	11.5	0.200		"	"	"	"	"	"	
Nickel	8.89	0.400		"	"	"	"	"	"	
Silver	0.0323	0.0200		"	"	"	"	"	"	
Zinc	34.2	0.400		"	"	"	"	"	"	
Selenium	ND	0.260		"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:35**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chromium, Hexavalent	ND	0.30		mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:35**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Calcium	21.3	0.0500		mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	15.7	0.0500		"	"	"	"	"	"	
Sodium	61.4	0.0500		"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

BKG04@2'
2403132-07 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **03/07/24 13:35**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	2.46	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:35**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	85.3		%	1	BHC0432	03/15/24	03/16/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:35**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.847	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:35**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.39		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

BKG04@5'
2403132-08 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:40**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Boron	ND	2.00		mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:40**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Arsenic	1.90	0.200		mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B	
Barium	24.0	0.400		"	"	"	"	"	"	
Cadmium	ND	0.200		"	"	"	"	"	"	
Copper	5.07	0.400		"	"	"	"	"	"	
Lead	6.51	0.200		"	"	"	"	"	"	
Nickel	4.95	0.400		"	"	"	"	"	"	
Silver	0.0225	0.0200		"	"	"	"	"	"	
Zinc	29.2	0.400		"	"	"	"	"	"	
Selenium	ND	0.260		"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:40**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chromium, Hexavalent	ND	0.30		mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:40**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Calcium	47.9	0.0500		mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	52.1	0.0500		"	"	"	"	"	"	
Sodium	61.4	0.0500		"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

BKG04@5'
2403132-08 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **03/07/24 13:40**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	1.46	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:40**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	94.2		%	1	BHC0432	03/15/24	03/16/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:40**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.544	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:40**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.24		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

BKG05@0.5'
2403132-09 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:45**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Boron	ND	2.00		mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:45**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Arsenic	5.35	0.200		mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B	
Barium	80.7	0.400		"	"	"	"	"	"	
Cadmium	0.329	0.200		"	"	"	"	"	"	
Copper	16.4	0.400		"	"	"	"	"	"	
Lead	11.6	0.200		"	"	"	"	"	"	
Nickel	7.19	0.400		"	"	"	"	"	"	
Silver	0.0538	0.0200		"	"	"	"	"	"	
Zinc	40.3	0.400		"	"	"	"	"	"	
Selenium	ND	0.260		"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:45**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chromium, Hexavalent	ND	0.30		mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:45**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Calcium	97.9	0.0500		mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	23.4	0.0500		"	"	"	"	"	"	
Sodium	58.0	0.0500		"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

BKG05@0.5'
2403132-09 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **03/07/24 13:45**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	1.37	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:45**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	84.0		%	1	BHC0432	03/15/24	03/16/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:45**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.582	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:45**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	7.88		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

BKG05@2'
2403132-10 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:50**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Boron	ND	2.00	mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:50**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Arsenic	8.28	0.200	mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B	
Barium	33.0	0.400	"	"	"	"	"	"	
Cadmium	0.279	0.200	"	"	"	"	"	"	
Copper	7.39	0.400	"	"	"	"	"	"	
Lead	10.4	0.200	"	"	"	"	"	"	
Nickel	6.03	0.400	"	"	"	"	"	"	
Silver	0.0355	0.0200	"	"	"	"	"	"	
Zinc	33.6	0.400	"	"	"	"	"	"	
Selenium	ND	0.260	"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:50**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Chromium, Hexavalent	ND	0.30	mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:50**

Analyte	Result	Reporting		Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit	Units						
Calcium	26.9	0.0500	mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	23.0	0.0500	"	"	"	"	"	"	
Sodium	78.9	0.0500	"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

BKG05@2'
2403132-10 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **03/07/24 13:50**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	2.70	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:50**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	86.8		%	1	BHC0432	03/15/24	03/16/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:50**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.564	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:50**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.17		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

BKG05@5'
2403132-11 (Soil)

Summit Scientific

Total Metals by EPA 6020B Hot Water Soluble Extraction

Date Sampled: **03/07/24 13:55**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Boron	ND	2.00		mg/L	1	BHC0511	03/15/24	04/05/24	EPA 6020B	

Total Metals by EPA 6020B

Date Sampled: **03/07/24 13:55**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Arsenic	1.95	0.200		mg/kg dry	1	BHC0681	03/19/24	03/25/24	EPA 6020B	
Barium	37.8	0.400		"	"	"	"	"	"	
Cadmium	0.209	0.200		"	"	"	"	"	"	
Copper	5.02	0.400		"	"	"	"	"	"	
Lead	10.2	0.200		"	"	"	"	"	"	
Nickel	5.99	0.400		"	"	"	"	"	"	
Silver	0.0244	0.0200		"	"	"	"	"	"	
Zinc	31.4	0.400		"	"	"	"	"	"	
Selenium	ND	0.260		"	"	"	"	"	"	

Hexavalent Chromium by EPA Method 7196

Date Sampled: **03/07/24 13:55**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Chromium, Hexavalent	ND	0.30		mg/kg dry	1	BHC0612	03/18/24	03/28/24	EPA 7196A	

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction

Date Sampled: **03/07/24 13:55**

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Calcium	34.8	0.0500		mg/L dry	1	BHC0843	03/21/24	04/22/24	EPA 6020B	
Magnesium	38.9	0.0500		"	"	"	"	"	"	
Sodium	52.2	0.0500		"	"	"	"	"	"	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

BKG05@5'
2403132-11 (Soil)

Summit Scientific

Calculated Analysis

Date Sampled: **03/07/24 13:55**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Sodium Adsorption Ratio	1.45	0.00100	units	1	BHD0807	04/23/24	04/23/24	Calculation	

Physical Parameters by APHA/ASTM/EPA Methods

Date Sampled: **03/07/24 13:55**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
% Solids	94.9		%	1	BHC0432	03/15/24	03/16/24	Calculation	

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction

Date Sampled: **03/07/24 13:55**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Specific Conductance (EC)	0.670	0.0100	mmhos/cm	1	BHC0845	03/21/24	03/24/24	EPA 120.1	

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction

Date Sampled: **03/07/24 13:55**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
pH	8.38		pH Units	1	BHC0844	03/21/24	03/24/24	EPA 9045D	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

Volatile Organic Compounds by EPA Method 8260B - Quality Control

Summit Scientific

Analyte	Reporting			Spike	Source	%REC		RPD		Notes
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	

Batch BHC0279 - EPA 5030 Soil MS

Blank (BHC0279-BLK1)

Prepared & Analyzed: 03/11/24

Benzene	ND	0.0020	mg/kg							
Toluene	ND	0.0050	"							
Ethylbenzene	ND	0.0050	"							
Xylenes (total)	ND	0.010	"							
1,2,4-Trimethylbenzene	ND	0.0050	"							
1,3,5-Trimethylbenzene	ND	0.0050	"							
Naphthalene	ND	0.0038	"							
Gasoline Range Hydrocarbons	ND	0.50	"							
<i>Surrogate: 1,2-Dichloroethane-d4</i>	0.0393		"	0.0400		98.2	50-150			
<i>Surrogate: Toluene-d8</i>	0.0392		"	0.0400		97.9	50-150			
<i>Surrogate: 4-Bromofluorobenzene</i>	0.0400		"	0.0400		100	50-150			

LCS (BHC0279-BS1)

Prepared & Analyzed: 03/11/24

Benzene	0.110	0.0020	mg/kg	0.100		110	70-130			
Toluene	0.125	0.0050	"	0.100		125	70-130			
Ethylbenzene	0.127	0.0050	"	0.100		127	70-130			
m,p-Xylene	0.254	0.010	"	0.200		127	70-130			
o-Xylene	0.122	0.0050	"	0.100		122	70-130			
1,2,4-Trimethylbenzene	0.119	0.0050	"	0.100		119	70-130			
1,3,5-Trimethylbenzene	0.120	0.0050	"	0.100		120	70-130			
Naphthalene	0.119	0.0038	"	0.100		119	70-130			
<i>Surrogate: 1,2-Dichloroethane-d4</i>	0.0373		"	0.0400		93.2	50-150			
<i>Surrogate: Toluene-d8</i>	0.0392		"	0.0400		98.1	50-150			
<i>Surrogate: 4-Bromofluorobenzene</i>	0.0402		"	0.0400		100	50-150			

Matrix Spike (BHC0279-MS1)

Source: 2402113-13

Prepared & Analyzed: 03/11/24

Benzene	0.103	0.0020	mg/kg	0.100	ND	103	70-130			
Toluene	0.117	0.0050	"	0.100	ND	117	70-130			
Ethylbenzene	0.117	0.0050	"	0.100	ND	117	70-130			
m,p-Xylene	0.230	0.010	"	0.200	ND	115	70-130			
o-Xylene	0.111	0.0050	"	0.100	ND	111	70-130			
1,2,4-Trimethylbenzene	0.104	0.0050	"	0.100	ND	104	70-130			
1,3,5-Trimethylbenzene	0.106	0.0050	"	0.100	ND	106	70-130			
Naphthalene	0.105	0.0038	"	0.100	ND	105	70-130			
<i>Surrogate: 1,2-Dichloroethane-d4</i>	0.0366		"	0.0400		91.4	50-150			
<i>Surrogate: Toluene-d8</i>	0.0398		"	0.0400		99.5	50-150			
<i>Surrogate: 4-Bromofluorobenzene</i>	0.0404		"	0.0400		101	50-150			

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

Volatile Organic Compounds by EPA Method 8260B - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source	%REC			RPD	Notes
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	

Batch BHC0279 - EPA 5030 Soil MS

Matrix Spike Dup (BHC0279-MSD1)	Source: 2402113-13			Prepared & Analyzed: 03/11/24						
Benzene	0.109	0.0020	mg/kg	0.100	ND	109	70-130	5.18	30	
Toluene	0.125	0.0050	"	0.100	ND	125	70-130	6.36	30	
Ethylbenzene	0.132	0.0050	"	0.100	ND	132	70-130	11.9	30	QM-07
m,p-Xylene	0.256	0.010	"	0.200	ND	128	70-130	10.6	30	
o-Xylene	0.123	0.0050	"	0.100	ND	123	70-130	9.75	30	
1,2,4-Trimethylbenzene	0.113	0.0050	"	0.100	ND	113	70-130	7.68	30	
1,3,5-Trimethylbenzene	0.116	0.0050	"	0.100	ND	116	70-130	9.60	30	
Naphthalene	0.108	0.0038	"	0.100	ND	108	70-130	3.38	30	
<i>Surrogate: 1,2-Dichloroethane-d4</i>	<i>0.0372</i>		<i>"</i>	<i>0.0400</i>		<i>93.0</i>	<i>50-150</i>			
<i>Surrogate: Toluene-d8</i>	<i>0.0387</i>		<i>"</i>	<i>0.0400</i>		<i>96.8</i>	<i>50-150</i>			
<i>Surrogate: 4-Bromofluorobenzene</i>	<i>0.0408</i>		<i>"</i>	<i>0.0400</i>		<i>102</i>	<i>50-150</i>			

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

Extractable Petroleum Hydrocarbons by 8015 - Quality Control
Summit Scientific

Analyte	Result	Reporting		Spike Level	Source		%REC		RPD		Notes
		Limit	Units		Result	%REC	Limits	RPD	Limit		

Batch BHC0282 - EPA 3550A

Blank (BHC0282-BLK1)

Prepared: 03/11/24 Analyzed: 03/12/24

C10-C28 (DRO)	ND	50	mg/kg								
C28-C36 (ORO)	ND	50	"								
Surrogate: <i>o</i> -Terphenyl	7.04		"	12.5	56.3	30-150					

LCS (BHC0282-BS1)

Prepared: 03/11/24 Analyzed: 03/12/24

C10-C28 (DRO)	379	50	mg/kg	500	75.9	70-130					
Surrogate: <i>o</i> -Terphenyl	7.48		"	12.5	59.8	30-150					

Matrix Spike (BHC0282-MS1)

Source: 2402113-13

Prepared: 03/11/24 Analyzed: 03/12/24

C10-C28 (DRO)	367	50	mg/kg	500	9.85	71.4	70-130				
Surrogate: <i>o</i> -Terphenyl	4.74		"	12.5	37.9	30-150					

Matrix Spike Dup (BHC0282-MSD1)

Source: 2402113-13

Prepared: 03/11/24 Analyzed: 03/12/24

C10-C28 (DRO)	383	50	mg/kg	500	9.85	74.5	70-130	4.23	20		
Surrogate: <i>o</i> -Terphenyl	4.93		"	12.5	39.4	30-150					

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

PAH by EPA Method 8270D SIM - Quality Control

Summit Scientific

Analyte	Result	Reporting		Spike Level	Source Result	%REC		RPD		Notes
		Limit	Units			%REC	Limits	RPD	Limit	

Batch BHC0324 - EPA 5030 Soil MS

Blank (BHC0324-BLK1)

Prepared: 03/12/24 Analyzed: 03/13/24

Acenaphthene	ND	0.00500	mg/kg							
Anthracene	ND	0.00500	"							
Benzo (a) anthracene	ND	0.00500	"							
Benzo (a) pyrene	ND	0.00500	"							
Benzo (b) fluoranthene	ND	0.00500	"							
Benzo (k) fluoranthene	ND	0.00500	"							
Chrysene	ND	0.00500	"							
Dibenz (a,h) anthracene	ND	0.00500	"							
Fluoranthene	ND	0.00500	"							
Fluorene	ND	0.00500	"							
Indeno (1,2,3-cd) pyrene	ND	0.00500	"							
Pyrene	ND	0.00500	"							
1-Methylnaphthalene	ND	0.00500	"							
2-Methylnaphthalene	ND	0.00500	"							
<i>Surrogate: 2-Methylnaphthalene-d10</i>	<i>0.0415</i>		"	<i>0.0333</i>		<i>125</i>		<i>40-150</i>		
<i>Surrogate: Fluoranthene-d10</i>	<i>0.0211</i>		"	<i>0.0333</i>		<i>63.3</i>		<i>40-150</i>		

LCS (BHC0324-BS1)

Prepared: 03/12/24 Analyzed: 03/13/24

Acenaphthene	0.0277	0.00500	mg/kg	0.0333		83.1		31-137		
Anthracene	0.0284	0.00500	"	0.0333		85.2		30-120		
Benzo (a) anthracene	0.0264	0.00500	"	0.0333		79.1		30-120		
Benzo (a) pyrene	0.0255	0.00500	"	0.0333		76.4		30-120		
Benzo (b) fluoranthene	0.0209	0.00500	"	0.0333		62.8		30-120		
Benzo (k) fluoranthene	0.0227	0.00500	"	0.0333		68.1		30-120		
Chrysene	0.0294	0.00500	"	0.0333		88.3		30-120		
Dibenz (a,h) anthracene	0.0383	0.00500	"	0.0333		115		30-120		
Fluoranthene	0.0240	0.00500	"	0.0333		72.0		30-120		
Fluorene	0.0271	0.00500	"	0.0333		81.4		30-120		
Indeno (1,2,3-cd) pyrene	0.0338	0.00500	"	0.0333		102		30-120		
Pyrene	0.0378	0.00500	"	0.0333		113		35-142		
1-Methylnaphthalene	0.0414	0.00500	"	0.0333		124		35-142		
2-Methylnaphthalene	0.0175	0.00500	"	0.0333		52.4		35-142		
<i>Surrogate: 2-Methylnaphthalene-d10</i>	<i>0.0362</i>		"	<i>0.0333</i>		<i>109</i>		<i>40-150</i>		
<i>Surrogate: Fluoranthene-d10</i>	<i>0.0243</i>		"	<i>0.0333</i>		<i>73.0</i>		<i>40-150</i>		

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

PAH by EPA Method 8270D SIM - Quality Control

Summit Scientific

Analyte	Reporting			Spike	Source	%REC		RPD		Notes
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	

Batch BHC0324 - EPA 5030 Soil MS

Matrix Spike (BHC0324-MS1)

Source: 2403132-01

Prepared: 03/12/24 Analyzed: 03/13/24

Acenaphthene	0.0155	0.00500	mg/kg	0.0333	ND	46.4	31-137			
Anthracene	0.0150	0.00500	"	0.0333	ND	45.0	30-120			
Benzo (a) anthracene	0.0147	0.00500	"	0.0333	ND	44.0	30-120			
Benzo (a) pyrene	0.0224	0.00500	"	0.0333	ND	67.2	30-120			
Benzo (b) fluoranthene	0.0178	0.00500	"	0.0333	ND	53.4	30-120			
Benzo (k) fluoranthene	0.0167	0.00500	"	0.0333	ND	50.1	30-120			
Chrysene	0.0159	0.00500	"	0.0333	ND	47.6	30-120			
Dibenz (a,h) anthracene	0.0342	0.00500	"	0.0333	ND	103	30-120			
Fluoranthene	0.0137	0.00500	"	0.0333	ND	41.0	30-120			
Fluorene	0.0154	0.00500	"	0.0333	ND	46.3	30-120			
Indeno (1,2,3-cd) pyrene	0.0382	0.00500	"	0.0333	ND	114	30-120			
Pyrene	0.0271	0.00500	"	0.0333	ND	81.2	35-142			
1-Methylnaphthalene	0.0276	0.00500	"	0.0333	ND	82.9	15-130			
2-Methylnaphthalene	0.0306	0.00500	"	0.0333	ND	91.8	15-130			
Surrogate: 2-Methylnaphthalene-d10	0.0212		"	0.0333		63.6	40-150			
Surrogate: Fluoranthene-d10	0.0140		"	0.0333		42.1	40-150			

Matrix Spike Dup (BHC0324-MSD1)

Source: 2403132-01

Prepared: 03/12/24 Analyzed: 03/13/24

Acenaphthene	0.0171	0.00500	mg/kg	0.0333	ND	51.3	31-137	10.1	30
Anthracene	0.0157	0.00500	"	0.0333	ND	47.0	30-120	4.22	30
Benzo (a) anthracene	0.0185	0.00500	"	0.0333	ND	55.4	30-120	22.9	30
Benzo (a) pyrene	0.0246	0.00500	"	0.0333	ND	73.9	30-120	9.53	30
Benzo (b) fluoranthene	0.0208	0.00500	"	0.0333	ND	62.5	30-120	15.7	30
Benzo (k) fluoranthene	0.0141	0.00500	"	0.0333	ND	42.3	30-120	16.8	30
Chrysene	0.0143	0.00500	"	0.0333	ND	42.9	30-120	10.3	30
Dibenz (a,h) anthracene	0.0357	0.00500	"	0.0333	ND	107	30-120	4.07	30
Fluoranthene	0.0165	0.00500	"	0.0333	ND	49.6	30-120	19.0	30
Fluorene	0.0134	0.00500	"	0.0333	ND	40.2	30-120	14.2	30
Indeno (1,2,3-cd) pyrene	0.0334	0.00500	"	0.0333	ND	100	30-120	13.3	30
Pyrene	0.0243	0.00500	"	0.0333	ND	73.0	35-142	10.6	30
1-Methylnaphthalene	0.0250	0.00500	"	0.0333	ND	75.0	15-130	9.99	50
2-Methylnaphthalene	0.0249	0.00500	"	0.0333	ND	74.7	15-130	20.6	50
Surrogate: 2-Methylnaphthalene-d10	0.0189		"	0.0333		56.8	40-150		
Surrogate: Fluoranthene-d10	0.0133		"	0.0333		40.0	40-150		

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

Total Metals by EPA 6020B Hot Water Soluble Extraction - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source	%REC		RPD		Notes
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	

Batch BHC0511 - EPA 3050B

Blank (BHC0511-BLK1)

Prepared: 03/15/24 Analyzed: 04/05/24

Boron ND 2.00 mg/L

LCS (BHC0511-BS1)

Prepared: 03/15/24 Analyzed: 04/05/24

Boron 4.78 2.00 mg/L 5.00 95.6 80-120

Duplicate (BHC0511-DUP1)

Source: 2403132-01

Prepared: 03/15/24 Analyzed: 04/05/24

Boron 0.146 2.00 mg/L 0.114 24.2 20 QR-01

Matrix Spike (BHC0511-MS1)

Source: 2403132-01

Prepared: 03/15/24 Analyzed: 04/05/24

Boron 4.93 2.00 mg/L 5.00 0.114 96.3 75-125

Matrix Spike Dup (BHC0511-MSD1)

Source: 2403132-01

Prepared: 03/15/24 Analyzed: 04/05/24

Boron 5.02 2.00 mg/L 5.00 0.114 98.1 75-125 1.73 25

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

Total Metals by EPA 6020B - Quality Control
Summit Scientific

Analyte	Result	Reporting		Spike Level	Source Result	%REC		RPD		Notes
		Limit	Units			%REC	Limits	RPD	Limit	

Batch BHC0681 - EPA 3050B

Blank (BHC0681-BLK1)

Prepared: 03/19/24 Analyzed: 03/25/24

Arsenic	ND	0.200	mg/kg wet							
Barium	ND	0.400	"							
Cadmium	ND	0.200	"							
Copper	ND	0.400	"							
Lead	ND	0.200	"							
Nickel	ND	0.400	"							
Silver	ND	0.0200	"							
Zinc	ND	0.400	"							
Selenium	ND	0.260	"							

LCS (BHC0681-BS1)

Prepared: 03/19/24 Analyzed: 03/25/24

Arsenic	37.2	0.200	mg/kg wet	40.0	93.1	80-120
Barium	38.7	0.400	"	40.0	96.8	80-120
Cadmium	2.04	0.200	"	2.00	102	80-120
Copper	43.0	0.400	"	40.0	108	80-120
Lead	19.7	0.200	"	20.0	98.5	80-120
Nickel	42.4	0.400	"	40.0	106	80-120
Silver	1.98	0.0200	"	2.00	98.8	80-120
Zinc	42.9	0.400	"	40.0	107	80-120
Selenium	3.47	0.260	"	4.00	86.8	80-120

Duplicate (BHC0681-DUP1)

Source: 2403132-01

Prepared: 03/19/24 Analyzed: 03/25/24

Arsenic	15.2	0.200	mg/kg dry	15.3	0.955	20	
Barium	54.6	0.400	"	55.9	2.37	20	
Cadmium	0.266	0.200	"	0.170	43.9	20	QR-04
Copper	3.85	0.400	"	4.90	23.8	20	QR-04
Lead	8.65	0.200	"	10.1	15.4	20	
Nickel	3.75	0.400	"	4.16	10.5	20	
Silver	0.0242	0.0200	"	0.0269	10.5	20	
Zinc	19.2	0.400	"	24.5	24.4	20	QR-04
Selenium	ND	0.260	"	ND		20	

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

Total Metals by EPA 6020B - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source		%REC		RPD		Notes
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit		

Batch BHC0681 - EPA 3050B

Matrix Spike (BHC0681-MS1)

Source: 2403132-01

Prepared: 03/19/24 Analyzed: 03/25/24

Arsenic	54.8	0.200	mg/kg dry	44.8	15.3	88.0	75-125				
Barium	90.8	0.400	"	44.8	55.9	77.8	75-125				
Cadmium	2.37	0.200	"	2.24	0.170	98.1	75-125				
Copper	32.9	0.400	"	44.8	4.90	62.5	75-125				QM-07
Lead	29.8	0.200	"	22.4	10.1	87.9	75-125				
Nickel	32.3	0.400	"	44.8	4.16	62.8	75-125				QM-07
Silver	2.18	0.0200	"	2.24	0.0269	96.0	75-125				
Zinc	50.1	0.400	"	44.8	24.5	57.2	75-125				QM-07
Selenium	3.24	0.260	"	4.48	ND	72.3	75-125				QM-07

Matrix Spike Dup (BHC0681-MSD1)

Source: 2403132-01

Prepared: 03/19/24 Analyzed: 03/25/24

Arsenic	54.3	0.200	mg/kg dry	44.8	15.3	86.8	75-125	0.955	25		
Barium	91.7	0.400	"	44.8	55.9	79.9	75-125	1.03	25		
Cadmium	2.39	0.200	"	2.24	0.170	99.1	75-125	0.979	25		
Copper	34.0	0.400	"	44.8	4.90	64.8	75-125	3.10	25		QM-07
Lead	30.0	0.200	"	22.4	10.1	88.8	75-125	0.685	25		
Nickel	33.4	0.400	"	44.8	4.16	65.3	75-125	3.37	25		QM-07
Silver	2.19	0.0200	"	2.24	0.0269	96.5	75-125	0.493	25		
Zinc	51.5	0.400	"	44.8	24.5	60.3	75-125	2.79	25		QM-07
Selenium	3.18	0.260	"	4.48	ND	71.0	75-125	1.86	25		QM-07

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

Hexavalent Chromium by EPA Method 7196 - Quality Control
Summit Scientific

Analyte	Reporting			Spike	Source		%REC		RPD		Notes
	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit		

Batch BHC0612 - 3060A Mod

Blank (BHC0612-BLK1)

Prepared: 03/18/24 Analyzed: 03/28/24

Chromium, Hexavalent ND 0.30 mg/kg wet

LCS (BHC0612-BS1)

Prepared: 03/18/24 Analyzed: 03/28/24

Chromium, Hexavalent 23.8 0.30 mg/kg wet 25.0 95.4 80-120

Duplicate (BHC0612-DUP1)

Source: 2403132-01

Prepared: 03/18/24 Analyzed: 03/28/24

Chromium, Hexavalent ND 0.30 mg/kg dry ND 20

Matrix Spike (BHC0612-MS1)

Source: 2403132-01

Prepared: 03/18/24 Analyzed: 03/28/24

Chromium, Hexavalent 28.6 0.30 mg/kg dry 28.0 ND 102 75-125

Matrix Spike Dup (BHC0612-MSD1)

Source: 2403132-01

Prepared: 03/18/24 Analyzed: 03/28/24

Chromium, Hexavalent 28.6 0.30 mg/kg dry 28.0 ND 102 75-125 0.196 20

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

Soluble Nutrients by EPA 6020/USDA60 6(2) - Saturated Paste Extraction - Quality Control

Summit Scientific

Analyte	Result	Reporting		Spike Level	Source Result	%REC		RPD		Notes
		Limit	Units			%REC	Limits	RPD	Limit	

Batch BHC0843 - General Preparation

Blank (BHC0843-BLK1)

Prepared: 03/21/24 Analyzed: 04/22/24

Calcium	ND	0.0500	mg/L wet							
Magnesium	ND	0.0500	"							
Sodium	ND	0.0500	"							

LCS (BHC0843-BS1)

Prepared: 03/21/24 Analyzed: 04/22/24

Calcium	5.79	0.0500	mg/L wet	5.00		116	70-130			
Magnesium	4.98	0.0500	"	5.00		99.7	70-130			
Sodium	5.00	0.0500	"	5.00		100	70-130			

Summit Scientific

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

Physical Parameters by APHA/ASTM/EPA Methods - Quality Control


Summit Scientific

Analyte	Result	Reporting		Spike	Source	%REC		RPD		Notes
		Limit	Units	Level	Result	%REC	Limits	RPD	Limit	

Batch BHC0432 - General Preparation

Duplicate (BHC0432-DUP1)	Source: 2403124-06	Prepared: 03/15/24	Analyzed: 03/16/24		
% Solids	77.7	%	75.6	2.74	20

Summit Scientific



The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline
 Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

Specific Conductance by EPA Method 120.1, Saturated Paste Extraction - Quality Control
Summit Scientific

Analyte	Result	Reporting		Spike Level	Source		%REC		RPD		Notes
		Limit	Units		Result	%REC	Limits	RPD	Limit		

Batch BHC0845 - General Preparation

Blank (BHC0845-BLK1)

Prepared: 03/21/24 Analyzed: 03/24/24

Specific Conductance (EC) ND 0.0100 mmhos/cm

LCS (BHC0845-BS1)

Prepared: 03/21/24 Analyzed: 03/24/24

Specific Conductance (EC) 0.145 0.0100 mmhos/cm 0.150 96.7 95-105


Duplicate (BHC0845-DUP1)

Source: 2403130-01

Prepared: 03/21/24 Analyzed: 03/24/24

Specific Conductance (EC) 0.130 0.0100 mmhos/cm 0.120 7.99 20

Summit Scientific



The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
 PO Box 1289
 Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
 Project Manager: Paul Henchan

Reported:
 04/23/24 15:00

Physical Parameters by APHA/ASTM/EPA Methods, Saturated Paste Extraction - Quality Control

Summit Scientific

Analyte	Result	Reporting		Spike	Source	%REC		RPD		Notes
		Limit	Units	Level	Result	%REC	Limits	RPD	Limit	

Batch BHC0844 - General Preparation

LCS (BHC0844-BS1)

Prepared: 03/21/24 Analyzed: 03/24/24

pH	9.17	pH Units	9.18	99.9	95-105
----	------	----------	------	------	--------


Duplicate (BHC0844-DUP1)

Source: 2403130-01

Prepared: 03/21/24 Analyzed: 03/24/24

pH	8.48	pH Units	8.53	0.588	20
----	------	----------	------	-------	----

Summit Scientific



The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



Fremont Environmental
PO Box 1289
Wellington CO, 80549

Project: Chevron - Howard USX A09-13 Flowline

Project Number: UWRWE-A3602-ABN
Project Manager: Paul Henchan

Reported:
04/23/24 15:00

Notes and Definitions

- QR-04 The RPD value for the sample duplicate or MS/MSD was outside of QC acceptance. QC batch accepted based on LCS and/or LCSD recovery and/or RPD values.
- QR-01 Analyses are not controlled on RPD values from sample concentrations less than 10 times the reporting limit. QC batch accepted based on LCS and/or LCSD QC results.
- QM-07 The spike recovery was outside acceptance limits for the MS and/or MSD. The batch was accepted based on acceptable LCS/LCSD recovery.
- DET Analyte DETECTED
- ND Analyte NOT DETECTED at or above the reporting limit
- NR Not Reported
- dry Sample results reported on a dry weight basis
- RPD Relative Percent Difference